

**सौरभ गर्ग**

वैज्ञानिक अधिकारी एवं  
प्रभारी, आयरमॉन केन्द्रीय नियंत्रण कक्ष  
विकिरण संरक्षा प्रणाली प्रभाग



भारत सरकार  
Government of India

**Saurabh Garg**

Scientific Officer &

Officer -In-Charge, IERMON Central Station  
Radiation Safety Systems Division

Ref: BARC/RSSD/IERMON/2018/632

August 02, 2018

**INVITATION OF QUOTATION**  
for  
**Repair jobs at IERMON Central Station**

Quotations are invited for termite treatment and refurbishment of furniture as per details, specification, quantity and Terms & Conditions mentioned in Annexure-A.

Your quotation in sealed cover, super-scribed with "Quotation for Repair jobs at IERMON Central Station", should be addressed to undersigned, sent to following address by Registered post or Speed post:

**IERMON Central Station**  
**CT&CRS Building, AERB Complex**  
**Anushaktinagar, Mumbai 400094**

Your quotation, signed by authorized signatory with official seal of the firm, should reach at above mentioned address by **August 16, 2018**.

(Saurabh Garg)

To,  
Selected Parties

Encl: As above





**Annexure – A**

| Sr. No. | Description of Job  | Qty     |
|---------|---|---------|
| 1       | Dismantling, alteration and reinstallation of existing Aluminium partition with supply and installation of additional required quantity of 14G aluminium extruded sections, 6mm thick frosted/etched glass panel. Additional quantity should be of approved make, model and color.          | 150 sft |
| 2       | Dismantling, alteration, reinstallation of existing false ceiling with supply and installation of additional required quantity of sections, aluminium tiles. Additional quantity should be of approved make, model and color.   | 125 sft |
| 3       | Removing existing PVC tiles and fixing new 3mm thick UV coated PVC flooring in wooden finish and of approved make and color.  | 125 sft |
| 4       | Dismantling, alteration, reinstallation of existing acoustic panelling with supply and installation of additional required quantity. Job involves making new wooden frame, fixing new 8mm thick acoustic sheets, matching to the existing panels and duly approved, with required hardware. | 100 sft |
| 5       | Cleaning/ Shampooing of existing acoustic panelling.  | 650 sft |
| 6       | Repair and refurbishment of termite infected furniture. The job also includes installation of new 10 thick pinboard with felt lining / 8 mm thick magnetic white board.   | 60 sft  |
| 7       | Cleaning and anti termite treatment to room no. 315 (Size: 17' x 17'). The job also involves dismantling of existing furniture, treatment and reassembly of furniture.  | Lumpsum |
| 8       | Supply and installation of roller blinds of approved colour and finish at MAC.  | 480 sft |

**Terms and Conditions:**

1. All components/items should be as per site requirement and should match with other installed setup, so as to merge with existing infrastructure.
2. If interested, parties may contact undersigned for a site survey for better understanding of requirement, with prior approval.
3. Quotation should clearly mention vendor's PAN, GST registration number, applicable HSN Code of material/supply.
4. Payment terms, warranty clause and validity of quotation shall be clearly mentioned.
5. This work may attract concessional rate of GST at the rate of 5%, as notified by government of India. In such case, BARC will issue the exemption certificate for the same. Vendors who are not willing to accept this condition shall mention the same clearly in their quotation.
6. Basic amount and taxes (with applicable percentage) shall be mentioned separately in the quotation. Final amount (including taxes) shall be mentioned both in figure and words.
7. Specific terms and condition, if any, should be clearly mentioned in the quotation.



(Saurabh Garg)  
OIC, IERMON Central Station